

भा०क०अनु०प०-केन्द्रीय भेड एवं ऊन अनुसंधान संस्थान, अविकानगर

सम्पदा अनुभाग

Es/Petty work/Misc/2017

dated 15-5-2017

निविदा सूचना

में _____

Sub-Proposal for repair works at Sector No 13 estimated cost- Rs.29, 547/- (for labour Charges only)

S/ N	particulars	Quantity (Apprx.)	Rates (Apprx.)	Cost
1	Earth work in excavation by mechanical means (Hydraulic excavator) manual means over areas(exceeding 30cm in depth 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50m and lift up to 1.5m ,disposed earth to be leveled and neatly dressed All kinds of soil	4.76 Cum		
2	Laying in position cement concrete including curing, compaction etc. complete in specified grade excluding the cost of centering and shuttering .All work up to plinth level. (1:5:10) using stone aggregate 20 mm size	6.31Cum		
3	Half brick masonry in superstructure above plinth level in cement mortar (1:4)	57.70 sqm		
4	Laying in position cement concrete including curing, compaction etc. complete in specified grade excluding the cost of centering and shuttering .All work up to plinth level. (1:3:6) using stone aggregate 20 mm size	1.00 cum		
5	Plaster on new surface on wall in cement sand mortar 1: 6 including racking of joints etc.12 mm thick	154.53 sqm		
06	Dismantling of old floor (1:2:4) including stacking of debris with in 50 m lead.	1.78 cum		
07	Laying 75 mm thick cement concrete flooring finished with floating coat of neat cement including cement slurry ,making of lines or grooves etc.	47.28 sqm		
08	Erection of chain link fencing 100x100x3.15 mm including tightening with screws, nut, etc to the angle iron.	85.68 sqm		
	Total			

(S.C.Gupta)
STO (Estate Section)